









Jon L. Devereaux

AIR - 4.3.4.1

NADEP Jacksonville Materials Engineer

including suggestions for reducing	ompleting and reviewing the collect this burden, to Washington Headqu uld be aware that notwithstanding ar DMB control number.	arters Services, Directorate for Infor	mation Operations and Reports	, 1215 Jefferson Davis	Highway, Suite 1204, Arlington	
1. REPORT DATE AUG 2001	2. REPORT TYPE		3. DATES COVERED 00-00-2001 to 00-00-2001			
4. TITLE AND SUBTITLE		5a. CONTRACT NUMBER				
HVOF as a Hard C		5b. GRANT NUMBER				
				5c. PROGRAM ELEMENT NUMBER		
6. AUTHOR(S)				5d. PROJECT NUMBER		
				5e. TASK NUMBER		
				5f. WORK UNIT NUMBER		
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) Naval Air Depot Jacksonville,AIR 4.3.4.1,Jacksonville,FL,32212				8. PERFORMING ORGANIZATION REPORT NUMBER		
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)				10. SPONSOR/MONITOR'S ACRONYM(S)		
				11. SPONSOR/MONITOR'S REPORT NUMBER(S)		
12. DISTRIBUTION/AVAII Approved for publ	LABILITY STATEMENT ic release; distributi	on unlimited				
_	OTES of Hard Chrome Pla d by SERDP/ESTCI		ew Meeting, Aug	ust 28-30, 200	01, Toronto,	
14. ABSTRACT						
15. SUBJECT TERMS						
16. SECURITY CLASSIFIC	17. LIMITATION OF ABSTRACT	18. NUMBER OF PAGES	19a. NAME OF RESPONSIBLE PERSON			
a. REPORT unclassified	b. ABSTRACT unclassified	c. THIS PAGE unclassified	Same as Report (SAR)	16	RESI UNSIBLE FERSUN	

Public reporting burden for the collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and

Report Documentation Page

Form Approved OMB No. 0704-0188





Current Status of P-3 Main Landing Gear

HVOF MLG Piston installed 26 April 99 on VP-30 Aircraft BuNo 156522

Aircraft completed PDM at NADEP JAX on 5 Dec 99

PDM extended due to multiple spar cap insertions

850 Landings on HVOF coated MLG Piston (Aug 00)

HVOF Coated Piston removed from service Aug 00 due to internal oil leak on ID-2 (NOT HVOF COATED)

HVOF Coated Strut repaired, sent back to VP-30 Installed on Aircraft 160284 STBD April 25, 2001 1,078 Total Landings on HVOF coated strut (8/23/01)



















Second P-3 MLG Piston HVOF coated

- Second P-3 MLG Piston coated with WC/Co 83/17 HVOF coating
- To be used in \$2M P-3 aircraft SLAP/SLEP Full Scale Fatigue Test
- R/H MLG chrome plated
- L/H MLG HVOF coated
- HVOF coating, grinding & processing of gear funded by Naval Research Lab (NRL)
- HVOF coated MLG Assy. installed on A/C
- Testing to begin September 2001 (24 month test)























Current Status and Recent Accomplishments

P-3 Bomb Bay Door Actuator Pistons coated, ground,
 & superfinished

 Four HVOF coated P-3 Bomb Bay Door Actuator Assemblies RFI and installed on VP-30 Aircraft BuNo 156510 July 2001

Aircraft currently undergoing PDM at JAX

A/C scheduled for delivery back to VP-30 on 7 Sept 01







Current Status of HVOF Coated EA-6B Main Landing Gear Flight Clearance

MLG Collar and Piston coated Oct. 99
Components completed depot processing Dec. 99
Flight clearance requested Jan 00
Meeting at NAVAIR/Pax River 13 April 00
Obtained NAVAIR approval of data May 00
Flight clearance at AIR 4.3.3 waiting final approval






"NAVAIR ONLY" HVOF L.G. meeting 16 Nov 00 Flight clearance on-hold NAVAIR presented 240KSI requirement for all landing gear fatigue tests at Dec HCAT mtg. NAVAIR & NRL meeting 29 Jan 01 Large sample (2"-3" dia) testing discussed NAVAIR (Eui Lee) to conduct testing Flight clearance at AIR 4.3.3 waiting final approval











Current Status of E-6A Main Landing Gear

Two HVOF coated E-6A MLG Uplock Hook Shafts installed 10 March 99 on A/C 164388

1,750 Flight Hours (8/02/01) A/C completed

1,524 Landings (8/02/01) Mod in Waco, TX

One HVOF coated E-6A MLG Uplock Hook Shaft installed on Aircraft 162784 in Feb. 2000

2,172 Flight Hours (7/31/01)

1,752 Landings (7/31/01)





E-6A MLG Lock Hook Shaft P/N 9-45196







Status of New HVOF Cell at NADEP JAX

Specification for HVOF Cell complete Contract Award - March 29, 2000 Cell to be completed July 2001 Natural Gas Line completed to Cell Blast cabinets for Cell #7 operational Jan 01 Sound-proof enclosed room installed Exhaust plenum & Air Handling System installed FANUC 5-Axis Robot System for Cell #7 installed Multi-Coat Process Control Unit Installed **Awaiting Filters for Natural Gas Line**